

ZAHL-PETROLEUM MAINTENANCE CO.

DIV. OF DAN LARSON ENTERPRISES, INC.

DISTRIBUTORS OF

PETROLEUM HANDLING EQUIPMENT AND INDUSTRIAL SUPPLIES

www.zahl-pmc.com



JOB: E-85

-PAGE 1 OF 3-

EQUIPMENT


1	4,000 GALLON STI-P3 TANK 7' X 14'	\$2,825.00
1	TANK I.D. MARKER	12.00
1	PP4-2 TEST STATION	165.00
1	23 2" VENT	13.00
1	15 GALLON BG SPILL MANHOLE	415.00
1	61SO OVERFILL TUBE	328.00
1	633 / 634 FILL CAP / ADAPTER	45.00
1	18" MONITOR MANHOLE	75.00
1	36" SUB MANHOLE	230.00
1	¾ HP AG E-85 SUB PUMP	895.00
1	MECHANICAL LEAK DETECTOR	255.00
1	SUB CONTROL BOX	80.00
1	TOKHEIM H322CR 1-PRODUCT DISPENSER WITH: 1 HOSE PER SIDE	4,970.00
2	5/8" X 9'6" HOSE, NOZZLE, SWIVEL, BREAKAWAY, SPLASH	230.00
1	VEEDER ROOT TLS350 WITH PRINTER WITH: (1) PROBE MODULE / 24-HOUR CSLD (3) MAG-1 PROBES (1) MAG-1 PROBE E85 (4) FLOAT KITS, RISER CAPS	8,128.00
-1	TRADE-IN OF 3-TANK VEEDER ROOT TLS250	-1,100.00
1	'U' BUMPER VENT	<u>90.00</u>
	EQUIPMENT SUB TOTAL	\$17,656.00
	FREIGHT	650.00
	TAX	<u>1,890.00</u>
	EQUIPMENT TOTAL	\$20,196.00

(CONTINUED ON NEXT PAGE)

3101 SPRING STREET N.E. • MINNEAPOLIS, MN 55413

PHONE: (612) 331-8550 • FAX: (612) 331-8553

EQUAL OPPORTUNITY EMPLOYER



ZAHL-PETROLEUM MAINTENANCE CO.

DIV. OF DAN LARSON ENTERPRISES, INC.

DISTRIBUTORS OF

PETROLEUM HANDLING EQUIPMENT AND INDUSTRIAL SUPPLIES

www.zahl-pmc.com



E-85

-PAGE 2 OF 3-

SCOPE OF WORK

OBTAIN PERMITS, NOTIFY MPCA AND GOPHER ONE.
DEMO CONCRETE / ASPHALT FOR NEW TANK, HAUL OUT RUBBLE.
EXCAVATE, PROVIDE AND SET (1) 4,000 GALLON SINGLE WALL STI-P3 TANK.
BACKFILL WITH CLEAN SAND AND COMPACT.
HAUL OUT EXCESS SOILS.
PROVIDE AND INSTALL OVERFILL / OVERSPILL PROTECTION.
TRENCH TO FIRST ISLAND AREA AND TO BUILDING.
INSTALL CONDUIT / WIRING FOR SUB PUMP, TANK PROBE AND DISPENSER.
CHANGE OUT VEEDER ROOT TLS250 FOR TLS350.
INSTALL SINGLE WALL FIBERGLASS PIPE AND TIE INTO PREVIOUSLY INSTALLED LINE.
BACKFILL TRENCHES AND COMPACT.
POUR 870 SQUARE FEET OF CONCRETE OVER TANK AND TRENCHES.
PROVIDE AND SET (1) TOKHEIM DISPENSER. PURGE AND CALIBRATE.
RE-CALIBRATE DISPENSER AFTER BREAK-IN PERIOD IF NECESSARY.
PRECISION TEST NEW PRODUCT LINE.

EQUIPMENT, TAX, FREIGHT	\$20,196.00
PERMITS, EXCAVATION, PIPING, ELECTRIC, CONCRETE	<u>25,755.00</u>
TOTAL	\$45,951.00

We propose to furnish material and/or labor in accordance with specifications and estimates – detail attached.

TOTAL: FORTY-FIVE THOUSAND NINE HUNDRED FIFTY-ONE AND 00/100 **\$45,951.00**

Note: This proposal may be withdrawn by us if not accepted within 30 days.

ACCEPTANCE OF PROPOSAL: The above prices, specifications and conditions are satisfactory and are hereby accepted.
You are authorized to do the work as specified. Payment will be made as outlined above.


Date of Acceptance: _____

Authorized Signature: _____

Customers Signature: _____

PAYMENT: 20% DOWN PAYMENT. BALANCE DUE NET 30 DAYS FROM INVOICE DATE AS WORK PHASES NOTE.
NOTE: EACH PAGE MUST BE READ AND INITIALED BY CUSTOMER.

(CONTINUED ON NEXT PAGE)



ZAHL-PETROLEUM MAINTENANCE CO.

DIV. OF DAN LARSON ENTERPRISES, INC.

DISTRIBUTORS OF

PETROLEUM HANDLING EQUIPMENT AND INDUSTRIAL SUPPLIES

www.zahl-pmc.com



E-85

-PAGE 3 OF 3-

EXCLUSIONS

ITEMS LISTED WILL BE TIME PLUS MATERIAL IF NOT STATED IN BID, UNLESS STATED OTHERWISE.

- ROCK REMOVAL, DEWATERING, TANK STRAPPING WITH HARDWARE, CONCRETE TIE TOWNS, UTILITY REPAIRS, TAPERING, SHORING, POOR SOIL CONDITIONS AND ANY UNFORESEEN OBSTRUCTIONS.
- ALL CONCRETE AND ASPHALT DEMO OVER 6" THICK OR WITH REBAR AND ANY UNFORESEEN CONCRETE UNDER ASPHALT AREAS.
- ANY ADDITIONAL CONCRETE OR ASPHALT REMOVAL AND REPLACEMENT OVER BID QUANTITIES.
- ALL SOIL TESTING AND / OR SOIL COMPACTION TESTING.
- CONTAMINATED SOIL REMOVAL, REPLACEMENT AND HAULING.
- IF EXISTING TANK BASIN AND / OR O.S.H.A. TAPERED AREA SOILS ARE NON-COMPACTABLE AND NEEDED OR WANTED TO BE REPLACED BY OWNER.
- NEW TANKS WILL BE THE OWNER'S RESPONSIBILITY TO FILL TO 90% FOR BALLAST TO KEEP TANKS FROM FLOATING AFTER BACKFILLING IS COMPLETED TO TANK TOP.
- ANY WORK REQUIRED TO EXISTING CONDUITS, WIRE, J-BOXES OR IF THEY ARE UNUSABLE.
- PAINTING OR DECALING IS NOT INCLUDED.
- ANY ASPHALT REPLACEMENT IS BY OTHERS.