ZAHL EQUIPMENT CO.

PEI

DIV. OF DAN LARSON ENTERPRISES, INC.
DISTRIBUTORS OF
PETROLEUM HANDLING EQUIPMENT AND INDUSTRIAL SUPPLIES

EQUIPMENT

1	4,000 GALLON SINGLE WALL FIBERGLASS TANK WITH 4 – STRAPS	$3,961.00
1	4' X 5' ISLAND FORM	61.00
1	36" SUB MANHOLES	216.00
1	¾ H.P. FE PETRO SUB PUMP	740.00
1	¾ H.P. CONTROL BOX	72.00
1	PUMP BOX 10" X 18"	69.00
1	61SO OVERFILL TUBE	299.00
1	5 GALLON B/G SPILL MANHOLE	320.00
1	633 / 634 CAP AND ADAPTER	42.00
1	23 2" VENT CAP	12.00
1	IMPACT VALVE	58.00
1	TOKHIEM DUAL SINGLE PRODUCT DISPENSER	5,500.00
2	HOSES, NOZZLE, SWIVELS, BREAKAWAYS, SPLASH GUARDS	240.00
1	18" MONITOR MANHOLE	75.00
1	MAG 1 PROBE	1,143.00
1	SUMP SENSOR WITH CONTROL MODULE	200.00
1	ENVIRON TANK SUMP SBS 3642	315.00
1	ENVIRON DISPENSER SUMP SDS 36916	317.00
1	ENVIRON SUMP ADAPTER TFA 4090	75.00

TANK AND ISLAND FREIGHT	350.00
SALES TAX	891.48
EQUIPMENT TOTAL	**$14,956.48**

E-85 OPTION

EXCAVATE FOR ADDITIONAL TANK. FORM AND POUR CONCRETE DEADMAN.
PROVIDE AND SET (1) 4,000 GALLON SINGLE WALL FIBERGLASS TANK.
INSTALL STRAPS, FILTER FABRIC, AND BACKFILL WITH PEA ROCK.
PROVIDE AND INSTALL TANK SUMP, SUB PUMP, OVERFILL AND OVERSPILL PROTECTION, SET AND POUR A 4' X 5' PUMP ISLAND.
INSTALL DOUBLE WALL ENVIROFLEX PIPING.
INSTALL CONDUIT / WIRE FOR SUB PUMP, DISPENSER AND TANK PROBE.
POUR ADDITIONAL 10' X 44' X 6" CONCRETE TANK PAD.

EXCAVATION, PIPING, ELECTRIC, CONCRETE	12,365.00
GRAND TOTAL	**$27,321.48**

We propose to furnish material and/or labor in accordance with specifications and estimates - detail attached.

TOTAL: TWENTY-SEVEN THOUSAND THREE HUNDRED TWENTY-ONE AND 48/100   **$27,321.48**

Note: This proposal may be withdrawn by us if not accepted within 30 days.
ACCEPTANCE OF PROPOSAL: The above prices, specifications and conditions are satisfactory and are hear by accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Date of Acceptance: _____

Authorized Signature: _____

Customers Signature: _____

PAYMENT: 20% DOWN PAYMENT, BALANCE DUE NET 30 DAYS FROM INVOICE DATE AS WORK PHASES NOTE:
NOTE: EACH PAGE MUST BE READ AND INITIALED BY CUSTOMER.